



NORTH DUM DUM MUNICIPALITY

163, M.B.ROAD, BIRATI, KOLKATA - 700051
PHONE: (033) 2514 - 2101 / 2514 - 2494, FAX - (033) 2514 - 2990
Website: <http://www.northdumdummunicipality.org>
E-mail ID: nddmboe@bsnl.in

Memo No:NDDM/WW/ 3779

Date: 29-8-19

Quotation Notice

Sealed Quotation are invited from reliable,resourcefull Contractor for Construction of valve chamber at Ward 10,34,5&1 of dimensions are as follows :

a) Valve Chamber, Inside Measurement : 900x900x1200mm, 250mm Wall Thickness - 5.00 nos

Terms and Conditions:


- i) Application in letter headed pad duly signed in. letter head should contain full address, telephone no, mobile no., fax & e-mail along with following technical Documents-
- ii) Quotation rate Schedule
- iii) Rate to be quoted both in Words & Figures and inclusive of all taxes and charges(**GST & CESS**)
- iv) Upto date Professional tax clearance receipts
- v) IT Pan card & Tax return receipts
- vi) Upto date GST registration certificate and valid Return certificate of the last quarter of the current financial year
- viii) Credential
- ix) The Authority reserves the right to accept or reject any or all Quotation without assiging any reasons whatsoever.

Application to be made for collecting Quotation Paper.

- 1)Last Date of Receiving Quotation: 07.09.2019 upto 3 P.M.
- 2)Date of Opening Quotation: 09.09.2019 at 4 P.M.

Quation Paper Dropping: At the office of Executive Officer Chamber.

Detailed information may be available from the Water Works Department and Municipality website (<http://www.northdumdummunicipality.org>).




FOR CONSTRUCTION OF VALVE CHAMBER
Inside measurement 900mmx900mmx1200mm. 250mm Thick Brick Wall (5.00
Nos)

SI No	Name of Work	Lenth(m)	Breadth(m)	Depth(m)	Qty	Unit	Rate Rs	Amount Rs
1	Earth Cutting	1.400	1.400	1.5	2.940	M3		
2	Single Brick Flat Soling	1.400	1.400		1.960	M2		
3	Plain Cement Concrete 1:3:6	1.400	1.400	0.075	0.147	M3		
4	250mm Brick Work 4:1	4.6	0.250	1.200	1.380	M3		
5	Shuttering Work	0.900	0.900		0.810			
		5.6		0.150	0.840			
					1.650	M2		
6	Reinforcement Work				55.00	kg		
7	Reinforced Cement Concrete 1:2:4	1.400	1.400	0.150	0.294	M3		
	12 mm dia @150mmc/c Box reinforcement both ways							

Cost of each valve chamber: Rs




 Signature of The Chairman
 North Dum DuM Municipality



**North Dum Dum Municipality
Birati, Kolkata- 700051**

**SCHEDULE FOR CONSTRUCTION OF VALVE CHAMBER UNDER NORTH DUM DUM
MUNICIPALITY**

Inside measurement 900mmx900mmx1200mm. 250mm Thick Brick Wall (5.00 Nos)

SI No	Name of Work	Lenth(m)	Breadth (m)	Depth(m)	Qty	Unit	Rate Rs	Amount Rs
1	Earth Cutting	1.400	1.400	1.500	2.940	M3		
2	Single Brick Flat Soling	1.400	1.400		1.960	M2		
3	Plain Cement Conc (1:3:6)	1.400	1.400	0.075	0.147	M3		
4	250 mm Brick Work 4:1	4.600	0.250	1.200	1.380	M3		
5	Shuttering Work	0.900	0.900		0.810	M2		
		5.600		0.150	0.840	M2		
					1.650	M2		
6	Reinforcement work				55.000	Kg		
7	Rein forced Cement Conc.(1:2:4)	1.400	1.400	0.150	0.294	M3		
	Total Amount					Rs		
						Say Rs		
						Rs		
	12 mm dia @150mmc/c Box reinforcement both ways							

Cost Of Each Valve Chamber : Rs

For 5.00 Nos Valve Chamber : Rs

Adding 12% GST : Rs

Adding 1% Cess : Rs

Total Rs

Say Rs