



NORTH DUM DUM MUNICIPALITY

163, M.B.ROAD, BIRATI, KOLKATA - 700051
PHONE: (033) 2514 - 2101 / 2514 - 2494, FAX - (033) 2514 - 2990
Website: <http://www.northdumdummunicipality.org>
E-mail ID: nddmboc@bsnl.in

Memo No:NDDM/WW/ 3786

Date: 31.08.19

Quotation Notice

Sealed Quotation are invited from reliable, resourcefull, Contractor for Construction of valve chamber at different places at Ward 5,1,32,6&10 of dimensions are as follows :

- a) Valve Chamber, Inside Measurement 900x900x1200mm, 250mm Wall Thickness – 5.00 nos
- b) Valve Chamber, Inside Measurement 750x750x900mm, 125mm Wall Thickness – 2.00 nos

Terms and Conditions:


- i) Application in letter headed pad duly signed in. letter head should contain full address, telephone no., mobile no., fax & e-mail along with following technical Documents-
- ii) Quotation rate Schedule
- iii) Rate to be quoted both in Words & Figures and inclusive of all taxes and charges(**GST & CESS**)
- iv) Up to date Professional tax clearance receipts
- v) IT Pan card & Tax return receipts
- vi) Up to date GST registration certificate and valid Return certificate of the last quarter of the current financial year
- viii) Credential
- ix) The Authority reserves the right to accept or reject any or all Quotation without assigning any reasons whatsoever.

Application to be made for collecting Quotation Paper.

- 1)Last Date of Receiving Quotation: 12.09.2019 upto 3 P.M.
- 2)Date of Opening Quotation: 13.09.2019 at 4 P.M.

Quation Paper Dropping: At the office of Executive Officer Chamber.

Detailed information may be available from the Water Works Department and Municipality website (<http://www.northdumdummunicipality.org>).



FOR CONSTRUCTION OF VALVE CHAMBER
Inside measurement 900mmx900mmx1200mm. 250mm Thick Brick Wall (5.00
Nos)

SI No	Name of Work	Lenth(m)	Breadth(m)	Depth(m)	Qty	Unit	Rate Rs	Amount Rs
1	Earth Cutting	1.400	1.400	1.5	2.940	M3		
2	Single Brick Flat Soling	1.400	1.400		1.960	M2		
3	Plain Cement Concrete 1:3:6	1.400	1.400	0.075	0.147	M3		
4	250mm Brick Work 4:1	4.6	0.250	1.200	1.380	M3		
5	Shuttering Work	0.900	0.900		0.810			
		5.6		0.150	0.840			
					1.650	M2		
6	Reinforcement Work				55.00	kg		
7	Reinforced Cement Concrete 1:2:4	1.400	1.400	0.150	0.294	M3		
	12 mm dia @150mmc/c Box reinforcement both ways							

Cost of each valve chamber: Rs


FOR CONSTRUCTION OF VALVE CHAMBER
Inside measurement 750mmx750mmx900mm. 125mm Thick Brick Wall (2.00
No)

SI no	Name Of The Work	Length(m)	Breadth (m)	Depth(m)	Qty	Unit	Rate Rs	Amount Rs
1	Earth cutting	1.000	1.000	1.15	1.150	M3		
2	Single Brick Flat Soling	1.000	1.000		1.000	M2		
3	Plain Cement Concrete 1:3:6	1.000	1.000	0.075	0.075	M3		
4	250mm Brick Work 4:1	3.5	0.000	0.900	3.150	M3		
5	Shuttering Work	0.750	0.750		0.563			
		4		0.100	0.400			
					.963	M2		
6	Reinforcement Work				12.00	Kg		
7	Reinforced Cement Concrete 1:2:4	1.000	1.000	0.100	0.100	M3		
	12 mm dia @150mmc/c Box reinforcement both ways							

Cost of each valve chamber: Rs



Signature of The Chairman
 North Dum DuM Municipality





North Dum Dum Municipality
Birati, Kolkata- 700051

SCHEDULE FOR CONSTRUCTION OF VALVE CHAMBER UNDER NORTH DUM DUM MUNICIPALITY

Inside measurement 900mmx900mmx1200mm. 250mm Thick Brick Wall (5.00 Nos)

SI No	Name of Work	Lenth(m)	Breadth (m)	Depth(m)	Qty	Unit	Rate Rs	Amount Rs
1	Earth Cutting	1.400	1.400	1.500	2.940	M3		
2	Single Brick Flat Soling	1.400	1.400		1.960	M2		
3	Plain Cement Conc (1:3:6)	1.400	1.400	0.075	0.147	M3		
4	250 mm Brick Work 4:1	4.600	0.250	1.200	1.380	M3		
5	Shuttering Work	0.900	0.900		0.810	M2		
		5.600		0.150	0.840	M2		
					1.650	M2		
6	Reinforcement work				55.000	Kg		
7	Rein forced Cement Conc.(1:2:4)	1.400	1.400	0.150	0.294	M3		
	Total Amount					Rs		
						Say Rs		
	12 mm dia @150mmc/c Box reinforcement both ways							

Cost Of Each Valve Chamber : Rs

For 5.00 Nos Valve Chamber : Rs

Adding 12% GST : Rs

Adding 1% Cess : Rs

Total Rs

Say Rs



**North Dum Dum Municipality
Birati, Kolkata- 700051**

**SCHEDULE FOR CONSTRUCTION OF VALVE CHAMBER UNDER NORTH DUM DUM
MUNICIPALITY**

Inside measurement 750mmx750mmx900mm. 125mm Thick Brick Wall (2.00 Nos)

SI No	Name of Work	Lenth(m)	Breadth (m)	Depth(m)	Qty	Unit	Rate Rs	Amount Rs
1	Earth Cutting	1.000	1.000	1.150	1.150	M3		
2	Single Brick Flat Soling	1.000	1.000		1.000	M2		
3	Plain Cement Conc (1:3:6)	1.000	1.000	0.075	0.075	M3		
4	125 mm Brick Work 4:1	3.500	0.000	0.900	3.150	M2		
5	Shuttering Work	0.750	0.750		0.563			
		4.000		0.100	0.400			
					0.963	M2		
6	Rein forcement work				12.000	Kg		
7	Rein forced Cement Conc.(1:2:4)	1.000	1.000	0.100	0.100	M3		
	Total Amount					Rs		
						Say Rs		
	12 mm dia @150mmc/c Box reinforcement both ways							

Cost Of Each Valve Chamber : Rs

For 5.00 Nos Valve Chamber : Rs

Adding 12% GST : Rs